

---

# **Installation of Wastewater Treatment Systems**

Consortium of Institutes for  
Decentralized Wastewater Treatment

First Edition

---

## Acknowledgements

This work was supported, in part, by the National Decentralized Water Resources Capacity Development Project (NDWRCDP) with funding provided by the U.S. Environmental Protection Agency through a Cooperative Agreement (WPA No. X-830851-01-0) with Water Environment Research Foundation (WERF) in Alexandria, Virginia. These materials have not been reviewed by the U.S. Environmental Protection Agency, NDWRCDP, or WERF. The contents of these materials do not necessarily reflect the views and policies of the NDWRCDP, WERF, or the U.S. Environmental Protection Agency, nor does the mention of trade names or commercial products constitute their endorsement or recommendation for use.

© Copyright 2009 by the Consortium of Institutes for Decentralized Wastewater Treatment. All rights reserved. Permission to copy must be obtained from the Consortium of Institutes for Decentralized Wastewater Treatment.

This document was reviewed by a panel of independent experts selected by the Consortium of Institutes for Decentralized Wastewater Treatment. Mention of trade names or commercial products does not constitute CIDWT, WERF nor EPA endorsement or recommendations for use. Similarly, omission of products or trade names indicates nothing concerning CIDWT's, WERF's or EPA's positions regarding product effectiveness or applicability. Neither WERF nor EPA, members of WERF, the organization(s) named below, nor any person acting on their behalf: (a) makes any warranty, expressed or implied, with respect to the use of any information, apparatus, method, or process disclosed in this report or that such use may not infringe on privately owned rights; or (b) assumes any liabilities with respect to the use of, or for damages resulting from the use of, any information, apparatus, method, or process disclosed in this report.

The Consortium of Institutes for Decentralized Wastewater Treatment acknowledges the contribution of the individuals who have provided input towards development of this manual. The project team also thanks the many manufacturers and vendors of products that provided information, figures, and slides about proper installation of their technologies and products. Without their contribution, these materials would not contain the breadth of information describing installation of wastewater treatment systems.

### The team developing these materials includes:

#### Primary Writers

Sara Christopherson, University of Minnesota  
Nancy Deal, North Carolina State University  
David Kalen, University of Rhode Island  
Bruce Lesikar, Texas AgriLife Extension Service  
David Lindbo, North Carolina State University  
George Loomis, University of Rhode Island  
Rebecca Melton, Texas AgriLife Extension Service

#### Secondary Writers

John Buchanan, University of Tennessee  
Kitt Farrell-Poe, University of Arizona  
David Gustafson, University of Minnesota  
Janet Hygnstrom, University of Nebraska  
Randy Miles, University of Missouri

### Official Installation Practitioner Review Committee

David Burnham, Burnham Excavating, Inc.  
Kenneth Davis, Axis Enterprises, Inc.  
Anthony Gaudio, Apalachee Backhoe and Septic Tank, LLC  
Scott Greene, Guilford County Health Department  
Eric Larson, Septic Check, Inc.  
Albert Mills, Orange County Environmental Health Dept.  
Mark Ritter, Ritter Sewer and Excavating  
Kyle Shern, BioGard, Inc.  
Tim Stasiunas, Advanced Wastewater Technologies, Inc.  
Bill Stuth, Jr., Stuth Company

### Project Review Group

James Converse, Professor Emeritus, University of Wisconsin  
Jerry Stonebridge, National Onsite Wastewater Recycling Association  
Tony Smithson, National Environmental Health Association  
Bill Stuth, Sr., Aqua Test, Inc.

### Additional Reviewers:

James Anderson, Ph.D. PSS, University of Minnesota  
Colin Bishop, Bord na Mona Environmental Products U.S., Inc.  
Tom Boekeloo, NYSDEC, New York  
Karen Borgeson, SJE-Rhombus  
Fred Bowers, Bureau of Nonpoint Pollution Control  
Tom Brandt, New Mexico Environment Department  
Matthew E. Byers, Ph.D., Zoeller Company  
Kevin Christianson, SJE-Rhombus  
Kurt Christopherson, Pipeline Supply  
Tom Espersen, Crow Wing County  
Rod Frederick, EPA Retired,  
Roxanne Groover, Florida Onsite Wastewater Association  
Dennis Hallahan, Infiltrator Systems, Inc.  
Adrian Hanson, Ph.D., P.E., New Mexico State University  
Adrian E. Hemby, Jr.  
Doug Hensarling, Aerobic System Inspection & Maintenance  
Mark Hooks, R.S., Infiltrator Systems, Inc.  
Kenneth D. Kerri, Office of Water Programs, California State University  
Jim Lashinski, Lashinski Services  
Robert E. Lee, Loudoun County Environmental Health  
Eva J. Loomis, Keene State College  
Ramzi Mahmood, Office of Water Programs, California State University  
Darren Meyers, Zoeller Company  
Katherine Morris, R.S., P.G., February Associates, Inc.  
Jon Olson, Olson's Excavating  
Rich Piluk, R.S. Anne Arundel County David Potts, Geomatrix, LLC  
James Prochaska, P.E., JNM Technologies, Inc.  
Barbara Rich, R.S., Deschutes County Environmental Health  
Ginger Shaffer, R.S., Shaffer Environmental Consulting, LLC  
Jeff Snowden, P.E., Snowden Onsite Services, Inc.  
David Theobald, Zoeller Company  
Daniel Tucker, Mining & Petroleum Training Services  
Thomas E. Yeagar, Kennedy/Jenks Consultants

### Publication layout and distribution:

MidWest Plan Service (MWPS)  
Website: [www.mwps.org](http://www.mwps.org)  
Phone: 800-562-3618 or 515-294-4337  
Fax: 515-294-9589  
E-mail: [mwps@iastate.edu](mailto:mwps@iastate.edu)



# Contents

<b>Preface</b>	<b>1</b>	Regulatory framework	17
Program scope, development and implementation	2	Licensing of professionals	18
<b>Chapter 1. Overview</b>	<b>3</b>	Permitting	18
Introduction	3	Design review and approval	18
Onsite wastewater treatment systems	3	Inspection	18
Key members of the onsite wastewater treatment system management team	5	Documentation	19
The professional installer	6	Management limitations	19
Functioning as a professional installer	7	Professional roles in the management program	20
Significance of proper installation	7	Summary of building a model	21
Public and environmental health	7	Industry integrity	21
System reliability	8	A comparison of ethics and law	21
Customer satisfaction	9	Building or losing credibility, respect, and admiration	21
Use of the installer training program by the onsite wastewater treatment system industry	9	Personal, public, and peer group perceptions of ethics	22
Overall system evaluation	10	Summary of ethics and integrity	22
Contact information	10	<b>Chapter 3. Safety</b>	<b>23</b>
Job contracting	11	Introduction	23
Design review	11	Federal and state OSHA standards	24
Site review	12	First aid and emergency response	25
Bidding and contracting	12	Personal protection	26
System planning and installation	13	Personal protective equipment	26
Summary	14	Personal hygiene	27
Form 1.1. Installation checklist: System evaluation	15	Pathogens and viruses	27
		Ergonomics	27
		General site issues	28
		Terrain	28
<b>Chapter 2. Business Models and Industry Integrity</b>	<b>17</b>	Vegetation	28
Introduction	17	Insects and snakes	28
Business models	17	Weather conditions	28
		Utility location	28

Cell phones	29	Vegetation	58
Electrical hazards	29	Soil and site description summary	58
Transporting equipment and materials	30	Water movement and soil treatment	58
Equipment-specific issues	30	Loading rates	60
Excavation and trench safety	31	Sediment and erosion control, stormwater and surface water management	62
Soil classification	31	Summary	62
Required protective measures	33		
Sloping	33		
Shoring	33		
Shielding	34		
Benching	34		
Access and egress	34		
Personal protective equipment	34		
Stability of adjacent structures	35		
Water accumulation	36		
Clear line of sight	36		
Placement of excavated material	36		
Re-inspection of trenches	36		
Confined space and hazardous atmospheres	37		
Materials hazards	38		
Ground surface spill response	38		
Additional hazards	39		
Summary and conclusions	39		
Form 3.1. Installation checklist— Safety	40		
<b>Chapter 4. Soil and Site Concepts for Installers</b>	<b>43</b>		
Introduction	43		
What is soil and why is it important?	45		
Important soil properties	46		
Horizons	47		
Soil texture	48		
Soil structure	50		
Grade	50		
Size	51		
Type	51		
Soil consistence	52		
Soil color	53		
Depth to limiting conditions	53		
Significant site conditions	54		
Slope	54		
Topography, landscape position, and landscape description	55		
Aspect	57		
Climatic and weather considerations	58		
		<b>Chapter 5. Construction Materials and Techniques</b>	<b>63</b>
		Introduction	63
		Equipment considerations for installers	63
		Equipment maintenance	64
		Ground pressure	64
		Wheeled equipment	65
		Tracked equipment	65
		Excavation equipment	65
		Backhoe	65
		Excavator	66
		Buckets and attachments	66
		Skid steer loader	66
		Dozer	67
		Trencher and borer	67
		Equipment safety requirements	68
		Material selection issues	68
		Storing materials	68
		Treatment media — sand	68
		Sieve analysis	69
		Uniformity coefficient and effective size	70
		ASTM C33 sand	70
		Soil grading curve classifications	70
		Field tests for sand quality	70
		Moisture and sand	71
		Distribution and drainage media — washed rock	72
		Geotextile fabric	72
		Bedding materials	72
		Cover media — soil treatment area backfill	73
		Techniques for installing a soil treatment area under different site conditions	73
		Erosion control	73
		Installation on wet sites	74
		Installation to maintain natural soil conditions	77

Installing systems in cold climates	77	Site-specific items	103
Installation at the proper elevation and grade	78	Bonding/Insurance	103
Excavation and over-excavation	78	Payment plan	104
Bedding	80	Installation planning: Construction planning and staging, job scheduling, and job staging	104
Installing on slopes	80	Construction planning	104
Procedures for system abandonment	81	Permits	104
Summary	83	Utilities	105
<b>Chapter 6. Planning</b>	<b>85</b>	Inspections	105
Introduction	85	Other professionals	105
Initial design/plan review	87	Cooperating with other trades	105
Components of a plan	87	Component preassembly	105
Title section	87	Ordering components	105
Site plan	87	Safety plan	106
Soil treatment area cross section	90	Bonding/Insurance secured	106
System profile	90	Payment plan implemented	106
Notes	90	Construction staging	106
Component details	92	Utilities located	106
References	92	Materials storage	106
Soil and site evaluation report	94	Spoils	106
Hydraulic loading	95	Water availability	106
Organic loading	95	Electricity	107
Buoyancy calculation	95	Weather	107
Treatment train components	95	Components, equipment, and tools	107
Site review	96	Job scheduling	107
Typography evaluation	96	Construction notification to local authority	107
Drainage	96	Utility markings	107
Monitoring wells	97	Equipment	108
Drinking water	97	Materials	108
Existing improvements	97	Components	108
Vegetation/obstruction management	97	Personnel	108
Removing landscaping features/trees	98	Weather	108
Soil conditions	98	Job staging	108
Soil treatment area (STA)	98	Bench mark	108
Plumbing stub-out	98	Property lines	108
Site layout	99	Verification of topography/drainage	109
Owner interview during plan and site review	99	Plumbing stub-out	109
Components of a bid	101	System components stake out	109
Material take-off	101	Utility location	109
Material source	102	Horizontal setbacks	110
Site restoration	102	Final inspection plan	110
Special equipment	102	Summary	110
Subcontractors	103		
Regulatory issues	103		

Form 6.1. Installation checklist: Planning	111	<b>Chapter 8. Watertight Piping and Tanks</b>	<b>139</b>
<b>Chapter 7. Distribution</b>	<b>115</b>	Watertight piping for wastewater conveyance	140
Introduction	115	Common pipe materials	140
Distribution and the infiltrative surface	116	Ductile iron	140
Loading rates	117	High density polyethylene	140
Effluent delivery over time and space	119	Acrylonitrile butadiene styrene	141
Effluent delivery in gravity distribution	119	Clay and orangeburg	141
Effluent delivery in pressure distribution	120	Polyvinyl chloride	141
Appropriate use of gravity and pressure distribution according to site limitations	121	Focus on PVC Piping	141
Typical system configurations for gravity distribution	121	PVC standard dimensions and materials	141
Parallel distribution	121	Nominal diameters	141
Sequential and serial distribution	123	Iron pipe standard—IPS	141
Installation of components for gravity distribution	124	Material codes	142
Gravity distribution devices	124	ASTM International	142
Trenches	126	ASTM D-1785 — Schedule 40, 80, and 120	142
Alternating valves	126	D-2241 — Pressure rated, standard dimension ratio	142
Typical system configurations for pressure distribution	126	PVC pipe	142
Pressure-dosed gravity distribution	126	SDR and schedule comparison	142
Low-pressure distribution in soil treatment areas	127	Additional plastic pipe standards	143
Pressure distribution in media filters	127	PW and DWV	143
Drip distribution	128	Pipe marking and identification	143
Installation of components for pressure distribution	128	Pipe colors	144
System and pump curves	128	Fittings and joints	144
Dosing stages and feed configurations	130	Connecting pipe and fittings	145
Density of delivery devices	131	Solvent-welding	145
Manifolds	131	Threaded connections	147
Valves	133	Mechanical joints	147
Laterals and orifices	134	Gaskets	148
Sleeved laterals	135	Electrical conduit	148
Access for management	136	Handling and storing	148
Distribution and drop boxes	136	Installation of piping systems	148
Inspection ports	136	Cleanouts	148
Manifold cleanouts and pressure ports	137	Insulation	149
Lateral cleanouts	137	Pipe cutting	149
Protecting soil properties	138	Embedment and embedment methods	150
Summary	138	Tracer wire	152
		Pipe testing	152
		Sleeving pipe	152
		Thrust blocks and mechanical connections	153
		Piping installation checklist	154

Form 8.1. Installation checklist:		Upflow anaerobic media filters	222
Piping	158	Recirculating media filters	223
Tanks overview	163	Trickling filters	226
Treatment tanks	163	Installation steps for media filters	228
Septic tanks	163	Form 10.1. Installation checklist:	
Grease traps	163	Media filters	244
Trash tanks	164	Media filter startup	247
Processing tanks	164	Understanding recirculation ratios	248
Dosing tanks	165	Setting recirculation ratios at system startup	249
Flow equalization tank	165	Form 10.2. Startup checklist:	
Recirculation tank	166	Media filters	252
Holding tank	167	Aerobic treatment units	254
Tank installation steps	168	Overview	254
Form 8.2. Installation checklist: Tanks	180	Treatment	254
Tank startup	183	Sequencing batch reactor	257
Form 8.3. Startup checklist: Tanks	185	Rotating biological contactor	257
		Adaptive mechanical aerator	257
<b>Chapter 9. Installation of Dosing Systems and Controls</b>	<b>187</b>	Installation	258
Overview	187	Form 10.3. Installation checklist:	
Pumps	188	Aerobic treatment unit	269
Pump selection	190	Startup steps	272
Pump discharge assembly	192	Form 10.4. Startup checklist:	
Controls	194	Aerobic treatment unit	274
Electrical safety	194	Constructed wetlands	276
Sensors	194	Overview	276
Dosing regimes	195	Treatment	276
Demand dosing	195	Installation	277
Timed dosing	197	Form 10.5. Installation checklist:	
Siphons	199	Constructed wetlands	284
Installation	201	Startup steps	286
Form 9.1. Installation checklist:		Form 10.6. Startup checklist:	
Demand and timed dosed pumps and siphons	207	Constructed wetlands	287
Startup	209	Lagoons	288
Form 9.2. Startup checklist:		Overview	288
Demand and timed dosed pumps and siphons	213	Treatment	288
		Installation	289
<b>Chapter 10. Advanced Treatment</b>	<b>217</b>	Form 10.7. Installation checklist:	
Overview	219	Lagoons	292
Media filters	219	Startup steps	293
How to use this media filter section	219	Form 10.8. Startup checklist: Lagoons	294
Overview	219	Disinfection	295
Media filter treatment trains	219	Chlorine	295
Single pass filters	220	Placement of chlorination units in the treatment train	295
		Tablet chlorinators	295

Liquid chlorinators	297	Form 11.6. Startup checklist: Drip field	360
Dechlorination	297	Spray field	363
Installation of chlorination and dechlorination units	297	Overview	363
Form 10.9. Installation checklist: Disinfection—chlorine	300	Treatment	364
Startup	301	Installation	365
Form 10.10. Startup checklist: Disinfection—chlorine	302	Form 11.7. Installation checklist: Spray field	368
Ultraviolet light	303	Startup	370
Overview	303	Form 11.8. Startup checklist: Spray field	372
Installation	304	Outfalls	374
Form 10.11. Installation checklist: Disinfection—ultraviolet light	307	Installation	374
Ultraviolet light startup	308	Form 11.9. Installation checklist: Outfalls	375
Form 10.12. Startup checklist: Disinfection—ultraviolet light	309	Outfall startup	376
		Form 11.10. Startup checklist: Outfalls	377
<b>Chapter 11. Soil Treatment Areas</b>	<b>311</b>	<b>Appendix A. Tables and Figures</b>	<b>379</b>
Introduction	312	Pipe specifications	379
Below- and above-grade	312	Friction loss	380
Below-grade	312	Pipe volume	383
Above-grade	314	Flow rate	383
Installation	315	Soil	386
Additional Documentation	329		
Summary	329	<b>Appendix B. Math Overview</b>	<b>389</b>
Form 11.1 Installation checklist: Soil treatment area (STA).	330	Preface	389
Startup	333	Math review	389
Form 11.2. Startup checklist: Soil treatment area (STA)	334	Relevant terms	389
Evapotranspiration (ET) beds	336	Units	390
Function	336	Basic calculations	392
Installation	336	Circumference	392
Form 11.3. Installation checklist: Evapotranspiration bed	341	Area	392
Startup	343	Volume of cubes or rectangular tanks	392
Form 11.4. Startup checklist: Evapotranspiration bed	344	Volume of a cylinder	394
Drip field	345	Volume of triangular shapes	394
Overview	345	Velocity in a pipe	394
Treatment	349	Friction loss in a pipe	395
Installation	349	Flow from an orifice	396
Form 11.5. Installation checklist: Drip field	355	Pump delivery rate (PDR)	396
Startup	358	Detention time	396
		Hydraulic loading rate	396
		Maximum burial depth	397
		Percentage	397
		Converting percent to a fraction	398
		Concentration	398

Calculating recirculation ratios at system startup	398		
<b>Appendix C. Volume Calculations</b>	<b>401</b>		
Media/Soil volume calculations	401		
Calculating the amount of media needed	401		
Cut and fill volume calculations	403		
<b>Appendix D. Slope Intersection Calculations</b>	<b>407</b>		
<b>Appendix E. Introduction to Surveying</b>	<b>411</b>		
Leveling basics	411		
Bench mark transfer	414		
Turning points	415		
Elevations/invert transfers	416		
		<b>Appendix F. Tank Buoyancy</b>	<b>419</b>
		<b>Appendix G. Watertightness Testing</b>	<b>425</b>
		Watertightness testing	425
		Hydrostatic testing	425
		Vacuum testing	426
		Testing existing tanks	426
		<b>Appendix H. Installer Glossary</b>	<b>429</b>
		<b>Appendix I. Onsite Wastewater Treatment System Malfunction</b>	<b>443</b>
		<b>References</b>	<b>447</b>
		<b>Index</b>	<b>449</b>

